



D	# OF STRUTS
6' to 8'	5 STRUTS
8.3" to 10'	6 STRUTS
10.3" to 12'	7 STRUTS
12.3" to 14'	8 STRUTS
14.3" to 16'	9 STRUTS
16.3" to 18'	10 STRUTS
18.3" to 20'	11 STRUTS

PLACE TWO STRUTS ON THE BOTTOM SECTION.
PLACE ONE STRUT ON ALL OTHER SECTIONS.








SECTION A-A
INSIDE ELEVATION
24'-2" MAX. DOOR WIDTH



SECTION THRU OPNG.

- NOTES:**
- * DOORS & HARDWARE WILL BE DESIGNED & MANUFACTURED & INSTALLED ACCORDING TO STANDARDS ESTABLISHED BY THE DOOR ACCESS SYSTEMS MANUFACTURING ASSOCIATION (DASMA).
 - * IN DOOR SECTIONS, WHERE WINDOW LITES ARE INSTALLED, STRUTS MAY BE RELOCATED OVER HINGE LEAFS TO AVOID OBSTRUCTION.
 - * AN INSIDE SLIDE LOCK SHOULD BE MOUNTED ON END STILE APPROXIMATELY 31" FROM BOTTOM OF DOOR ON THE INTERIOR LEFT.





TOP BRACKET DETAIL
DETAIL 1/S1.1

BOTTOM BRACKET DETAIL
DETAIL 2/S1.1

END HINGE DETAIL
DETAIL 3/S1.1


STRUT DETAIL
DETAIL 4/S1.1

JAMB BRACKET DETAIL
DETAIL 5/S1.1



MODELS: TAS III
DESIGN PRESSURE +12.4/-13.8 PSF
TEST PRESSURE +18.6/-20.7 PSF
TESTED PER THE APPLICABLE REQUIREMENTS OF:
ASTM: E 330 ANSID/ASMA 108-2002

NOTE: THE DESIGN OF SUPPORTING STRUCTURAL ELEMENTS SHALL BE THE RESPONSIBILITY OF THE PROFESSIONAL OF RECORD FOR THE BUILDING OR STRUCTURE IN ACCORDANCE WITH CURRENT BUILDING CODES



ENGINEERING DRAWING

TITLE	
24'-2" MAX. WIDTH, WIND LOAD RATED DOOR	
MODEL #	TAS-III, TR-III, AR-III, LP-III
SCALE	N/A
REV. NO.	0
SHEET	OF
DATE	